



**BUREAU
VERITAS**

1/2

Ref: BVIPL/SPL/BL/630/6/2017/162
Test Order dated: 07.06.2017

Date: 1.09.2017

M/s. United Office Systems Pvt. Ltd.,
Plot No. -62/1, 2 & 3, Vill-Vankas
Taluka-Umbergoan,
Dist. Valsad - 396150,
Gujarat


TEST REPORT ON ACCESS FLOORING SYSTEM

Source of sample / material : Access Flooring System verified at M/s United Office Systems Pvt. Ltd.
Customer reference : Email dated: 07.05.2017 and 1.09.2017
Date of test : 10.06.2017
Tests Conducted : Dynamic Loading Test
a. Soft body Impact Load Test, b. Hard body Impact Load Test
Sample Identification* : Steel Cementitious Panels with folded edge (Bare)
Product Model No.* : "UNITILE UFP 30 1650"
Product code No.* : "UNITILE UFP 30 1650 B 000 00 00000"
Equipment used* : Impact Load Test Machine
Panel size (Nominal)* : 600 mm x 600 mm
Thickness /Gross weight of Panel* : 30 mm/ 13.000 kg.
Test Method : BSEN 12825:2001(E) 5.5.2.5, 5.5.1.5
Witness by/Date of visit : Mr. Radhakrishna, Consultant
Bureau Veritas, India Pvt. Ltd, Bangalore on 10.6.17

TEST RESULTS

Table 1. Soft Body Impact Test

Sample Reference	UNITILE UFP 30 1650 Bare		BSEN 12825:2001(E) Clause 5.5.2.5 Requirement
	Center	Edge Center	
Location of Impact	Center	Edge Center	Soft body impact test on the system shall be with a load of 40 kgs dropped from a height of 1000 mm
Module Size(mm)	600x 600		
Test Height in mm	300		
Observation	PASS System didn't collapse on or after Impact		System Should not collapse on or after Impact


02/09/2017
SANJEEV PATGAR
Manager LAB

contd...../-

Ref: BVIPL/SPL/BL/630/6/2017/162
 Test Order dated: 07.06.2017

Date: 1.09.2017

Table 2. Hard Body Impact Test

Sample Reference	UNITILE UFP 30 1650 Bare			BSEN 12825:2001(E) Clause 5.5.1.5 Requirement
Location of Impact	Center	Center of edge	*weakest point	Hard body impact test on the system shall be with 4.50 kgs dropped from a height of 600 mm
Module Size(mm)	600×600			
Test Height in mm	300			
Observation	PASS System didn't collapse on or after Impact			System Should not collapse on or after Impact



UNITILE UFP 30 1650 Bare - TEST UNDER PROGRESS

* As furnished by the customer

- Note:
1. The results relate only to the items tested.
 2. Report shall not be reproduced, except in full without the written approval of the lab.
 3. Any correction invalidates this report.

for **BUREAU VERITAS (INDIA) PRIVATE LIMITED**
 Construction Services Laboratory

Sanjeev Patgar
 02/09/2017 **SANJEEV PATGAR**
 Manager LAB